




Test By: CK
 Reviewed By: LSB

Order Number G101659992
 Date 10/06/14 18:38:38

AC-1 Air Cleaner Testing Facility

Control Number 1409180907-002
 Test Number AC-14079 WACP300

Smoke Natural



TIME(MIN)	Cti	ln(Cti)	TIME(MIN)	Cti	LN(Cti)
0.00	33,477.71	10.42	11.00	32,641.00	10.39
1.00	33,403.56	10.42	12.00	32,517.64	10.39
2.00	33,461.30	10.42	13.00	32,387.02	10.39
3.00	33,331.00	10.41	14.00	32,310.36	10.38
4.00	33,167.25	10.41	15.00	32,197.41	10.38
5.00	32,903.50	10.40	16.00	31,924.50	10.37
6.00	33,067.87	10.41	17.00	32,012.52	10.37
7.00	32,858.69	10.40	18.00	31,872.13	10.37
8.00	32,759.00	10.40	19.00	31,653.17	10.36
9.00	32,510.07	10.39	20.00	31,727.94	10.36
10.00	32,608.19	10.39			


Quantity	Measured	Lower Limit	Upper Limit	Acceptable
Decay Constant	0.00283	-	-	
Slope Standard Deviation (cfm)	0.11	-	2.00	YES
Background at Injection (part/cc)	0.631	-	20.00	YES
Initial Concentration (part/cc)	33730	24000	35000	YES
Data points used	21	9	-	YES
Average Temperature (°F)	70	65	75	YES
Average Humidity (%RH)	39	35	45	YES
Average Input Voltage (volts)	0.0			
Average Test Unit Power (watts)	0.0			

--	--	--

AC-1 Air Cleaner Testing Facility

Control Number 1409180907-002
 Test Number AC-14079 WACP300

Smoke Measured



TIME(MIN)	Cti	ln(Cti)	TIME(MIN)	Cti	LN(Cti)
0.00	28,855.95	10.27 (eliminated - 95% pred.)	11.00	4,658.67	8.45
1.00	25,239.68	10.14	12.00	3,906.52	8.27
2.00	21,884.03	9.99	13.00	3,225.99	8.08
3.00	18,664.66	9.83	14.00	2,712.04	7.91
4.00	15,854.19	9.67	15.00	2,251.41	7.72
5.00	13,342.81	9.50	16.00	1,833.06	7.51
6.00	11,317.93	9.33	17.00	1,550.05	7.35
7.00	9,543.24	9.16	18.00	1,256.32	7.14
8.00	8,042.41	8.99	19.00	1,007.08	6.91
9.00	6,761.48	8.82	20.00	895.07	6.80
10.00	5,548.38	8.62			

Quantity	Measured	Lower Limit	Upper Limit	Acceptable
Decay Constant	0.17899	-	-	
Slope Standard Deviation (cfm)	1.33	-	18.04	YES
Background at Injection (part/cc)	3.786	-	20.00	YES
Initial Concentration (part/cc)	33393	24000	35000	YES
Data points used	20	9	-	YES
Average Temperature (°F)	70	65	75	YES
Average Humidity (%RH)	37	35	45	YES
Average Input Voltage (volts)	120.1			
Average Test Unit Power (watts)	61.2			

CADR	177.57		
CADR Standard Deviation	1.3	17.8	YES



Test By: CK
 Reviewed By: LSB

Order Number G101659992
 Date 10/20/14 15:08:28

AC-1 Air Cleaner Testing Facility

Control Number 1409180907-002
 Test Number AC-14079 WACP300

Operating Power

Quantity	Measured	Lower Limit	Upper Limit	Acceptable
Operating Power (watts)	60.2			
Operating Voltage (volts)	120.0	119	121	YES
Points Used	13	10		YES
Dust CADR	198.14			
Energy Star (CADR/Watt)	3.3	2.0		YES

Operating Power (watts)	60.2			
--------------------------------	-------------	--	--	--

